



M E M O R A N D U M

SUBJECT: Management Assistance Report
WMATA Crane Purchase
(MAR-23-0001)

DATE PUBLISHED: November 17, 2022

FROM: OIG – Rene Febles [REDACTED]

TO: GM/CEO – Randy Clarke

Executive Summary

The Office of Inspector General (OIG) is transmitting this Management Assistance Report (MAR) based on an allegation of wasteful spending of federal funds. This was associated with the Washington Metropolitan Area Transit Authority (WMATA) procurement of a \$3.8 million 35 Ton Crane-Rail Bound that did not perform as intended.

On September 17, 2010, Cranemasters, Inc. (Cranemasters) was awarded a contract to build a 35 Ton Crane-Rail Bound (RC35). The contract obligated Cranemasters to meet contract specifications and specified delivery times of the crane. Although RC35 was briefly utilized by WMATA, albeit unauthorized, in WMATA's view it failed to perform as intended and did not meet WMATA's engineering acceptance safety and performing requirements. To date, RC35 is sitting idle at the WMATA Greenbelt Rail Yard.

On August 12, 2022, this matter was forwarded to WMATA's GM/CEO for review and action as appropriate, not only because of the concern with the expenditure, but also because it presented a safety concern associated with the operability of this crane on the Metrorail system. On September 9, 2022, WMATA's Executive Vice President/Chief Operating Officer responded to this MAR agreeing to secure to the keys to the vehicle deeming it unusable by WMATA employees and indicating WMATA would perform an analysis to identify the most cost-effective way to dispose of RC35.

Background

On December 4, 2009, WMATA announced a request for proposal (RFP) using federal funds associated with the Federal Economic Recovery Stimulus Program to purchase a 35 Ton Crane-Rail Bound prototype. The prototype crane was intended to, among other capabilities, operate through 360 degrees of rotation when using outriggers and pick and carry a load throughout the Metrorail system without using outriggers. As a result, specifications for the crane were developed and incorporated into the RFP.

On September 17, 2010, Cranemasters was awarded contract ES10091, in the amount of \$3,838,880. Cranemasters was obligated to meet the contract specifications and deliver the final working crane in 420 days. The performance period was between September 17, 2010 and March 16, 2012.

A progress payment schedule was approved between WMATA and Cranemasters after six milestones were met post-award (**Exhibit 1**). WMATA paid Cranemasters \$383,888 on November 18, 2010; \$1,151,664 on August 2, 2011; \$767,776 on January 24, 2012; \$767,776 on November 6, 2012; and \$353,888 on December 10, 2013. According to the progress payment schedule, the last payment was set to be released to Cranemasters after they had delivered RC35; completed training to WMATA personnel; deliverables were received and accepted; and final acceptance testing was completed and approved.

On January 14, 2016, the Office of Track & Structures (TRST) wrote a memorandum stating, in part, that RC35 was built to specifications and delivered on time (**Exhibit 2**).

On January 27, 2016, the Office of Procurement and Materials (PRMT) notified Cranemasters that WMATA accepted receipt of RC35. In addition, PRMT advised that all of the deficiencies within the scope of the work referenced in the awarded contract were correct and completed (**Exhibit 3**). Since Cranemasters did not provide the required training to WMATA personnel, a total of \$30,000 was deobligated from the original contract amount. As a result, the final value was established at \$3,808,880.

Contract Technical Specification and Performance Issues

At the onset of RC35 being delivered to WMATA in 2013, several issues were identified with the crane. For example, records provided by the Office of Quality Assurance, Internal Compliance and Oversight (QICO) reflected in September 2013 that WMATA's Department of Transit Infrastructure and Engineering, Office of Quality and Assurance Warranty (QAAW) wrote a detailed inspection report to identify issues and ensure WMATA received a defect-free crane (**Exhibit 4**). WMATA personnel identified 59 workmanship and quality issues involving RC35. These issues included, but were not limited to: fluid leaking from flange at rear left of vehicle under deck; multiple hydraulic hose clamps exhibiting inconsistent hardware; insufficient thread protrusion on hydraulic hose clamps; seven of the eight axle keepers installed upside-down; corrosion and rust on several parts; inconsistent hardware used at forward tow loop weldment; hydraulic line clamps missing rectangular metal plates at the left side of car body; and the boom slide stop was not mounted flush against boom slide flange.

Additional records provided by QICO reflected that QAAW wrote another detailed report in September 2015 highlighting several out of compliance issues involving RC35 based on the technical specifications in the contract (**Exhibit 5**). These issues included, but were not limited to: the crane having no electronics for monitoring crane angle and load; no boom angle indication; swing overload limiter; jacking points called out on the machine; hydraulic leaks and routing issues throughout the crane; hazardous walkway to check engine oil; unprotected hose around the front and rear trucks; wire routing and labeling throughout the machine; no lights in dog house; right engine cover snags; undercarriage hoses and wires hanging; cab mirror violated envelope; counterweight cradle bent; and outrigger pad retaining pin damaged.

Moreover, according to a warranty/history report, RC35 continued to have performance issues (**Exhibit 6**). For example, in November 2015, RC35 was transported to a Cranemasters facility in Richmond, Virginia to address several of the open corrective actions. In October 2016, RC35 was transported to Greenbelt Rail Yard after Cranemasters addressed several open corrective actions and testing was completed. In December 2016, additional testing was to be scheduled; however, it was canceled due to the crane winch retracking at random. In January 2017, while RC35 was moving, the crane winched the block into the boom and broke the cable, which caused damage to the boom tip. During testing in April 2017, RC35 brakes would not hold on a hill in the forward direction, lost propulsion, and made loud grinding noises. In June 2017, data from testing found that the machine left travel mode for no reason, had intermittent connectivity issue to one of the interlock sensors, and found one axle's parking brake release pressure was in low in one direction. Finally, in December 2017, RC35 winch cable broke, the hook block fell to the ballast, and the cable whipped over to the back of the crane resulting in the crane headache ball falling between the Metrorail tracks (**Exhibit 7**). The operator was unable to brake, forcing him to shut down RC35.

In May 2018, the Office of Car Track Equipment Maintenance (CTEM) advised in a memorandum that they had resolved to make no further effort to support the endeavor to meet the requirements of Contract. (**Exhibit 8**). In WMATA's view, there remained "multiple significant functional and design items" over a five-year period. CTEM recommended RC35 be removed from WMATA and/or all areas of concern are resolved prior to reengagement with WMATA to complete acceptance testing. According to WMATA engineers, the continuous repairs needed to repair RC35 required an extensive allocation of additional WMATA resources to review and escort their repair efforts. Cranemasters continues to communicate with WMATA personnel to address concerns associated with RC35, to include, redesigning the crane; however, Cranemasters has only submitted plans that do not provide a permanent solution. OIG was unable to quantify the WMATA personnel costs to date. Furthermore, OIG was unable to quantify any future costs to accomplish repair requests made to Cranemasters so that RC35 could perform as intended.

To date, RC35 sits idle and unused at the Greenbelt Rail Yard since it has never performed as intended nor has it ever passed WMATA engineering acceptance safety and performing requirements, despite TRST and PRMT indicating that they met the contract requirements.

Safety Concern

OIG learned that several WMATA crane operators used RC35 on various projects throughout the Metrorail system after the crane was delivered sometime in 2013 (**Exhibit 9**). This usage occurred despite the crane not being officially authorized since it did not appear to meet with the technical specifications incorporated in the contract. The purpose of acceptance testing is to determine whether the RFP technical specifications in the contract were met to verify the crane is safe, operationally ready, and defect-free.

WMATA personnel explained that RC35 was controlled by TRST. This allowed TRST to utilize the crane whenever they wanted on projects. A WMATA engineer added that he learned from a prior crane operator that the crane was used on a project for acceptance testing without engineers' involvement. This engineer indicated that it is not normal practice to perform acceptance testing on a project as it is a liability issue. He gave an example that one would not want to lift 35 tons of material over people when one has not tested that the crane could hold 35 tons of material.

The prior Contracting Officer Technical Representative (COTR) for RC35 confirmed when the crane was delivered in 2013, TRST used it in a testing capacity. He recalled RC35 being used for switch installation jobs near West Falls Church Rail Yard and Shady Grove interlocking. A previous crane operator also confirmed that he operated RC35 along with Cranemasters on different projects after the crane was delivered. He indicated that when he used the crane, he was using it to remove certain sections of the interlocking. He recalled using RC35 at Greenbelt Rail Yard and on the mainline, though he could not recall exactly where.

In December 2019, OIG advised WMATA management of the complaint we received and requested WMATA not move or tamper with RC35. In a recent site visit, OIG observed RC35 still present at the Greenbelt Rail Yard with a tag indicating "DANGER, DO NOT REMOVE THIS TAG!" with remarks indicating tow only (**Exhibit 10**). OIG is concerned that RC35 was used on multiple TRST projects after WMATA inspectors uncovered numerous issues with the crane being out of compliance with the RFP technical specifications at the onset of the crane being delivered to WMATA and has never performed as intended.

This matter is being forwarded to you for review and action as appropriate as it represents safety concerns associated with the operability of this crane on the Metrorail system if used again.

Recommendations and Actions

OIG recommends that the General Manager and Chief Executive Officer:

1. Follow WMATA safety protocols regarding unsafe equipment and apply them to RC35.
2. Make a determination if RC35 can be utilized or must be disposed.

Please provide a response to OIG's recommendations by September 2, 2022 to Rene Febles, rfebles@wmataoig.gov.

Exhibits

1. RC35 progress payment schedule
2. Memorandum dated January 14, 2016 from TRST indicating in part, that RC35 was built to specifications and delivered on time
3. Memorandum dated January 27, 2016 from PRMT to Cranemasters notifying them that WMATA had accepted receipt of RC35
4. Quality Assessment Report conducted in September 2013
5. Quality Assessment Report conducted in September 2015
6. RC35 Warranty/History Report
7. Incident form related to RC35 in December 2017
8. Letter explaining that CTEM will no longer support the acceptance of RC35
9. RC35 Cranemasters photograph
10. RC35 photographs taken by OIG

cc: COO – B. Dwyer
COUN – P. Lee
MARC – E. Sullivan
SAFE – T. Impastato

Exhibit 1

CRANEMASTERS

**3001 Williamsburg Road
Richmond, Virginia 23231
(800) 624-0543**

www.cranemasters.com


September 9, 2010
CONTRACT ES10091/GWF
35 TON-RAILBOUND CRANE

PROGRESS PAYMENT SCHEDULE

Invoice #1	10% within 30 days after award of the contract.
Invoice #2	30% within 30 days after presentation and acceptance of approval drawings
Invoice #3	20% progress payment upon 10% total assembly complete
Invoice #4	20% progress payment upon 25% total assembly complete
Invoice #5	10% progress payment upon 50% total assembly complete
Invoice #6	10% Final payment after delivery of crane and after all training is complete and all deliverables received (spares, manuals) and accepted and after final acceptance testing complete and approved.

SPECIAL CONDITIONS:

- a. Each invoice amount above is to be computed as a percentage (%) against the total contract award value of \$3,838,880.
- b. Photos and progress reports to be provided by Cranemasters every month.
- c. Progress inspections are to be made by authorized WMATA personnel from start-up thru final assembly.
- d. Ten percent (10%) of contract value will be retained until crane is delivered, tested and WMATA officially accepts Crane. All deliverables - manuals, training and spares must be delivered and accepted prior to final payment.
- e. At no point prior to delivery, will total amounts invoiced exceed 90% of the total contract value.
- f. Allowance for overhead and profit will be included in all progress payments submitted.
- g. Invoices will be in lump sum amounts and are to be substantiated by delivery of digital photographs of progress made, or by site visits conducted by authorized WMATA personnel to the Cranemasters' manufacturing facility.
- h. **CHANGE ORDERS** -all change orders must be approved in writing by WMATA and Cranemasters. If a change order adds or detracts from the contract cost, a MOD will be issued to make the appropriate cost adjustment to the contract value.
- i. **DELIVERY** - Contract schedule requires delivery to WMATA's Alexandria yard within 420 days from date of award.


Kevin H. Green
WMATA Contracting Officer


Barry Isringhausen
Cranemasters Inc., Vice President

Exhibit 2

M E M O R A N D U M



SUBJECT: Contract No. ES10091
35 Ton Crane - Rail Bound

DATE: January 14, 2016

FROM: TRST - Leroy Jones 

TO: Contract File (ES10091)

Contract ES10091 was awarded to Cranemasters, Inc., on September 17, 2010 in the amount of \$3,838,880.00. The Final Contract Value was established at \$3,808,880.00. Currently all work required by the contract, consisting of the item listed below has been completed.

1. Build 35 Ton Crane to specifications, deliver on time and provide excellent support services throughout the useful life of the crane.

Concurred by:

Exhibit 3



January 27, 2016

Mr. Barry Isringhausen
Vice President
Cranemasters, Inc.
8020 Whitepine Road
North Chesterfield, Virginia 23237

Re: Contract No. ES10091
35 Ton Crane Rail Bound
Final Acceptance

Dear Mr. Isringhausen:

This letter is to inform you of the Authority's acceptance of the referenced contract.

The Authorized Representative of the Contracting Officer advises me that all deficiencies within the scope of work for the referenced contract are correct and completed

We appreciate your successful completion of the contract and look forward to your future participation in the Authority's construction program.

Sincerely,



Richard Owens
Contracting Officer
Office of Procurement and Materials

Washington
Metropolitan Area
Transit Authority

600 Fifth Street, NW
Washington, DC 20001
202/962-1234

www.metroopensdoors.com

A District of Columbia,
Maryland and Virginia
Transit Partnership

Exhibit 4



WASHINGTON METROPOLITAN AREA TRANSIT AUTHORITY
DEPARTMENT OF TRANSIT INFRASTRUCTURE & ENGINEERING SERVICES
OFFICE OF QUALITY ASSURANCE AND WARRANTY

QUALITY ASSESSMENT REPORT

REPORT NO.	AR-CENV-20130930-01	PERFORMED - DATES:	9/25/2013
ASSESSMENT PROJECT:	In-process Inspection of 35 Ton Crane Vehicle – Rail Bound	PROGRAM:	RFP ES10091/GWF
LOCATION:	Greenbelt Yard (CTEM)	PROGRAM MANAGER:	Michael Thomas (COTR)
DATE OF NOTIFICATION:	9/30/2013	PREPARED BY:	M. O'Hara

SUMMARY:

On 9/25/2013, QAAW performed an in-process inspection of the new, 35 Ton Crane Vehicle, currently undergoing final assembly at the Greenbelt Yard. This is a CTEM vehicle which is being provided by *Cranemasters*. The purpose of the inspection was to inspect the vehicle for discrepant areas of workmanship and quality. The vehicle was not inspected for design or engineering related issues. As such, numerous items (Qty: 59) were discovered and documented. The purpose of this report is to provide the COTR and *Cranemasters*, with a detailed inspection report in an effort for *Cranemasters* to correct the issues and ensure that WMATA receives a defect-free vehicle.

COMMENTS:

Please see the attached Inspection Report which contains 59 items and associated photos detailing the workmanship and quality issues discovered.

Follow Up Required: Yes

Date of Follow Up: 10/07/2013

REPORT DISTRIBUTION:

CENV: Reynolds, Kakkar, Thomas, Eisenhauer
CMNT: Cannon
CTEM: Hagan, Jones

QAAW Officer:

Michael O'Hara

QAAW Manager:

Audited Supervisor:

DATE: 9/30/2013

DATE:

DATE:



WMATA CTEM Equipment

No.

Inspection Report

Page: 1 Of 4

Car / Unit No.: <u>35 Ton Crane – Hi Rail Bound. (Reference AR-CENV-20130930-01)</u>	Shop Order No.: <u>RFP S10091/GWF</u>
Manufacturer: <u>Cranemasters</u>	Consultant: <u>LTK</u> WMATA Inspector: <u>O'Hara, Davis, Brown, Panik, Gunter & Achter</u>
Insp. Type: <u>In-process Inspection on WMATA Property (Greenbelt).</u>	R Inspector: <u>Gr elt</u>
Date: <u>25</u> day <u>09</u> month <u>2013</u> year	Location: <u>CTEM</u>

Item No.	Discrepancy	MFR QC <small>(Sign / Initial / Stamp)</small>	Cust Insp. <small>(Sign / Initial / Stamp)</small>
1	At each outrigger (4 places); yellow cable is in hard contact with cylinder and lacks protection rubber. Photo 1		
2	Nearly all tie-wraps exhibit sharp edges and trimming. Photo 2		
3	Multiple hydraulic hose clamps exhibit inconsistent hardware grade 5 and Grade 8 bolts are used throughout these clamps along outriggers the carbody. Photo 3A & 3B		
4	At pivot points where the hoses join the carbody there exists hard contact between the bolt head on the hydraulic clamps and nearby hydraulic hoses. Photo 4		
5	Multiple cases of insufficient thread protrusion on hydraulic hose clamps on hoses at pivot of outrigger. Photo 5		
6	Chafing conditions visible under carbody forward of forward right outrigger. Photo 6		
7	Electrical tape wrapped instead sharp edges of fitting on forward truck, right side, forward of #2. Photo 7		
8	P-clamp on cable is not attached to vehicle under carbody near forward right outrigger lock. Photo 8		
9	Compartment cover missing at bottom of radiator compartment. Photo 9		
10	Unpainted rusting mounting bracket at forward right headlight. Photo 10		
11	Unpainted and rusting mounting bracket at forward right red light. Photo 11		

12	Seven of the eight axle keepers are installed upside-down. Photos 12A & 12B		
13	Hydraulic line clamps are missing rectangular metal plates at pivot point of forward right outrigger. Photo 13		
14	Missing lockwasher under head of cap screw at hydraulic flange on right side of carbody (Service Brake Pilot hose). Photo 14		
15	Corrosion/rust on hydraulic flange near leveling cylinder on forward left side of vehicle. Photo 15		
16	Support pipe for manifold attached to leveling cylinder on forward left side of vehicle is rusted. Photo 16		
17	Inconsistent hardware used at forward tow loop weldment. Middle bolt is longer than the two on either side of it on left and right side. Photo 17		
18	Inconsistent hardware used at rear tow loop weldment. Middle bolt is longer than the two on either side of it on left and right side. Photo 17		
19	Electrical tape used to hold black protective conduit on yellow cable harness is unattached from conduit and is unraveled on right side of forward truck. Photo 18		
20	Fittings leaking fluid at forward left outrigger cylinder. Photo		
21	Insufficient thread protrusion on P-clamp hardware for sensor cable at #3 stabilizer cylinder on truck. Photo		
22	Fluid leaking from gaskets under carbody aft of left forward outrigger lock. Photo 21A & 21B		
23	Hydraulic lines for #3 stabilizer are not secured to truck frame at forward left area of truck. Photo 22		
24	At rear of vehicle under the deck and above the truck, large bundles of hoses in contact with the weldments for the front and rear tow-loops. Photo 23		
25	Tow-loop mounting hardware at front and rear of vehicle exhibit insufficient thread protrusion. Photo 24		
26	Nearly all of the large cap screws in turret of vehicle exhibit corrosion/rust. Photo 25		
27	Cap washers securing the right and left side outrigger controls have paint in the recess of the hex heads and appear to be marred. Photos 26A & 26B		
28	Hydraulic line clamps are missing rectangular metal plates at left side of carbody. Photo 27		

29	Paint in threads of P-clamp studs at left side of carbody, forward of #3 axle. Photo 28		
30	Large bundle of hydraulic lines chafe against white wear pad on deck of vehicle at rear left side. Photo 29		
31	Fluid leaking from flange at rear left of vehicle under deck. Photo 30		
32	Hard contact and damage has occurred between the suction hose and pony mot mounting brackets. Photo 31		
33	Inconsistent cap screws found on block on right rear leveling device – insufficient thread protrusion. Photo 32		
34	Loose nut on P-clamp stud at rear left side of carbody above axle. Photo 33		
35	Hose connection plates welded to deck aft of cab area are untested and tested. Photos 34A & 34B		
36	Insufficient thread protrusion on P-clamp studs on carbody, right side, above #3 axle. Photo 35		
37	Fluid leaking from flanges under deck, above axle, right side. Photo 36		
38	Cable lying on #3 axle, right side. Photo 37		
39	Jam nuts on boom sheave are untested and rusted. Photo 38		
40	Plugs/caps missing from bolt penetrating through holes on boom. Photo 39		
41	Sheave missing at end of boom. One side of the boom contains a small white sheave, but the other side is not, but there are holes where one may be installed. Photos 40A & 40B		
42	Boom slide stop is not mounted flush against boom slide flange. There exists a gap between these two parts. Photo 41		
43	Visible gap between upper sheave jam nuts at end of boom. Photo 42		
44	Random hardware (washers) found lying in turret area. Photo 43		
45	Engine filter access compartment contains multiple hoses in contact with each other and engine components. Photos 44A, 44B & 44C		

46	Terminals, wire and tie-wraps laying on the floor of the electrical compartment. Photos 45A & 45B		
47	Bolt laying on floor of radiator compartment. Photo 46		
48	In several areas, the hydraulic hose clamps pinch the hoses. Photo 47		
49	Unterminated wires at the terminal strip in the electrical compartment are not properly capped. Photo 48		
50	Fins on the surface of the radiator are bent/damaged at top. Photo 49		
51	Nearly all glass panels in the cab area lack rubber seals/glazing. Photo 50A, 50B, 50C, 50D, 50E, 50F & 50G		
52	Bottom cab windshield wiper is misaligned with the windshield and falls below the glass. Photo 51		
53	Cotter pin installed incorrectly on large pin securing stacked sheet steel rights at rear of vehicle. Photo 52		
54	Several fluid leaks exist directly below the cab area of the vehicle. Photo 53A & 53B		
55	Battery cable is in hard contact with threads of connector in turret of the vehicle. Photo 54		
56	Wiring in electrical compartment lacks labels and is poorly routed in general. Photos 55A, 55B & 55C		
57	Hardware on P-clip above pivot point of outrigger is loose. Photo 56		
58	Sheet metal connected to forward exterior side of the fuel tank has two P-clamps on it yet is not secured to anything. Photo 57		
59	"RC-01" labels are missing from the vehicle.		

113-F-059 Rev 1

SUPPORTING PHOTOS ATTACHED



Photo 3A



Photo 1




Photo 3B



Photo 2



Photo 6



Photo 4



Photo 7



Photo 5



Photo 10



Photo 8



Photo 11



Photo 9




Photo 13



Photo 12A



Photo 14



Photo 12B



Photo 17



Photo 15



Photo 18



Photo 16




Photo 21A



Photo 19




Photo 21B



Photo 20



Photo 24



Photo 22




Photo 25



Photo 23



Photo 27



Photo 26A




Photo 28




Photo 26B



Photo 31



Photo 29



Photo 32



Photo 30



Photo 34B



Photo 33



Photo 35



Photo 34A



Photo 38



Photo 36



Photo 39




Photo 37



Photo 41




Photo 40A



Photo 42



Photo 40B



Photo 44B



Photo 43



Photo 44C



Photo 44A



Photo 46



Photo 45A



Photo 47



Photo 45B



Photo 50A




Photo 48



Photo 50B



Photo 49



Photo 50E



Photo 50C



Photo 50F



Photo 50D



Photo 52



Photo 50G




Photo 53A



Photo 51



Photo 55A



Photo 53B




Photo 55B



Photo 54



Photo 57




Photo 55C



Photo 56

Exhibit 5



WASHINGTON METROPOLITAN AREA TRANSIT AUTHORITY
DEPARTMENT OF TRANSIT INFRASTRUCTURE & ENGINEERING SERVICES
OFFICE OF QUALITY ASSURANCE AND WARRANTY
QUALITY ASSESSMENT REPORT

REPORT NO.	AR-CTEM-20150908-01F	PERFORMED - DATES:	8/5/2015 8/26/2015
ASSESSMENT PROJECT:	35 Ton-Track Maintenance Rail bound Crane	PROGRAM:	CraneMasters
LOCATION:	Branch Ave	CTEM REP:	Steve Redman
DATE OF NOTIFICATION:	4/9/2015	PREPARED BY:	Ulysses Johnson

EXECUTIVE SUMMARY:

On 8/5/2015 and 8/26/2015 CTEM/CENV/QAAW along with representatives from CraneMasters met at the Branch Ave rail yard to discuss the remaining open items on the 35 Ton Track Maintenance Rail bound Crane (35 Ton Crane). The criterion for the open items was based on the Technical Specification section of *RFP ES10091/GWF*.

During the initial meeting WMATA's representatives presented a discrepancy list to the CraneMasters representative. CraneMasters technicians were on site and have worked diligently to address many of the open items. Currently there are 18 discrepancies that remain open.

The following are examples of some the open items that still need to be addressed.

- Hydraulic leaks and routing issues throughout the machine.
- Unprotected hose around the front and rear trucks
- Chaffing and hoses that are rubbing.

The attachment below provides a more detailed and in-depth information along with the status about the remaining open items. QAAW will continue to monitor the progress of the completed work and provide a status report.

ATTACHMENTS:

- Discrepancies
- Photo Support

Follow Up Required: Yes, repairs on-going

REPORT DISTRIBUTION:

CTEM: D. Hagan, J. Barrett, A. O'Dell

CENV: D. Lemke, D. Eisenhauer

QAAW: M. DiNatale, J. Panik, S. Silver, J. Hernet

QAAW Officer:

QAAW Manager:

DATE: 9/15/2015

DATE: 9/15/2015

DISCREPANCIES



QAAW

Quality Control Discrepancy List

Shop/ Location:	Branch Ave Yard		QAAW Inspector:	U. Johnson
Inspection:	CraneMasters 35 Ton Crane		Team Inspectors	A. O'Dell, G Mitchell D. Eisenhauer
Unit #:	RC35		CTEM Rep	J. Barrett, S.Redman
			Date:	8/26/2015
Item No	Discrepancy	RFP No. ES10091/GWF Spec#	Corrective Action	Status
1	No electronics for monitoring crane angle, load etc.	14.5	Parts on hand to be Installed	Electrical issues with the LMI system
2	No swing overload limiter	14.4	Parts on hand to be Installed	Parts installed - resolving calibration issues
3	Hydraulic leaks and routing issues throughout the machine need to be addressed	General	A list of discrepancies to be created and distributed to CraneMasters See Photo Support attachment	A meeting has been set to discuss the issues with Crane Master's mechanic
4	Hazardous walkway to check engine oil access	1.7	A proposed handrail will be installed	WMATA requested that a new design is proposed
5	Unprotected hose around the front and rear trucks	10.8	A list of discrepancies to be created and distributed to CraneMasters	Changes will be made after the LMI is up and running
6	Paint throughout the machine needs touchup	11.2	Open to be addressed after other parts are installed	Open



QAAW

Quality Control Discrepancy List

Shop/ Location:	Branch Ave Yard		QAAW Inspector:	U. Johnson
			Team Inspectors	A. O'Dell, G Mitchell D. Eisenhauer
Inspection:	CraneMasters 35 Ton Crane		CTEM Rep	J. Barrett, S.Redman
Unit #:	RC35		Date:	8/26/2015
Item No	Discrepancy	RFP No. ES10091/GWF Spec#	Corrective Action	Status
7	Hydraulic leak under turret opposite side of the cab	General	A list of discrepancies to be created and distributed to CraneMasters	A meeting has been set to discuss the issues with Crane Master's mechanic
8	Wire routing and labeling throughout the machine needs to be addressed.	11.1, 11.2	Open to be addressed after other parts are installed	Parts are on order - waiting on connectors
9	No lights in dog house	11.14	Open	Installation completed for all but one light.
10	Right engine cover snags	11.2	Parts are on order	Installation to be complete prior to delivery
11	Undercarriage hoses and wires hanging	11.2, 10.8	Open	Open
12	Cab mirror violates envelope. (Rear camera w/monitor?)	1.3	Camera is being installed	Camera installed needs WMATA final approval
13	Counterweight cradle bent	11.2	Parts on hand to be Installed	Parts installed waiting WMATA final approval
14	Needs remote drains for engine	General	Installed needs verification	Not completed



QAAW

Quality Control Discrepancy List

Shop/ Location:		Branch Ave Yard		QAAW Inspector:	U. Johnson
Inspection:		CraneMasters 35 Ton Crane		Team Inspectors	A. O'Dell, G Mitchell D. Eisenhauer
Unit #:		RC35		CTEM Rep	J. Barrett, S.Redman
				Date:	8/26/2015
Item No	Discrepancy	RFP No. ES10091/GWF Spec#	Corrective Action	Status	
15	No spare parts delivered	28	Open	Open	
16	Manual not finalized	31	80% complete	sent to WMATA for review	
17	Outrigger pad retaining pin damaged	General	Parts on site need to be tested	Open	
18	No weight markings are labeled on the counterweights	General	Labelling will be installed	Open	
19	Electrical panels not marked	13.5	Closed	Closed	
20	No boom angle indication (mechanical)	14.5	Will be relocated	Closed	
21	No centering indication for turret. No pins, locks or marks	21.2	Parts on Order to be installed	Closed	
22	No Jacking points called out on the machine	4.12	Pads to be welded to outriggers	Closed	
23	Minimum exposed bolt thread violation (tow eye fasteners)	2.2	Closed	Closed	



QAAW

Quality Control Discrepancy List

Shop/ Location:		Branch Ave Yard		QAAW Inspector:	U. Johnson
Inspection:		CraneMasters 35 Ton Crane		Team Inspectors	A. O'Dell, G Mitchell D. Eisenhauer
Unit #:		RC35		CTEM Rep	J. Barrett, S.Redman
				Date:	8/26/2015
Item No	Discrepancy	RFP No. ES10091/GWF Spec#	Corrective Action	Status	
24	All shutdown switches need large labels affixed	13.5	Labels and or decals will be added	Closed	
25	No labels for front or rear (A & B)	13.5		Closed	
26	Outrigger controls not labeled	13.5	Open	Closed	

PHOTO SUPPORT

Crane Master RC35


Noted issues:

08/26/2015


BY GARY MITCHELL

A close-up photograph of a vehicle's front gear box area. The metal surface is dark and shows signs of wear and oil leakage. A small, rectangular metal plate is attached to the surface, featuring a circular logo and the words 'Model', 'Date', and 'Oil'. The plate has some handwritten markings. The surrounding area is dimly lit, with a bright light source creating a strong reflection on the metal surface. The background shows a concrete floor and some mechanical components.

Front Gear box leak: Appears to be above drain plug.

A close-up photograph of a vehicle's right front stabilizer cylinder. The cylinder is a vertical, cylindrical metal component, likely made of steel, showing signs of wear and rust. It is mounted on a dark, textured metal base. The background is dark and shows some mechanical parts and a yellow safety bar. The lighting is focused on the cylinder, highlighting its texture and the surrounding components.

Right Front Stabilizer cylinder leaking.

A close-up photograph of a vehicle's brake master cylinder assembly. The master cylinder is a cylindrical metal component with a yellow arrow pointing to its top. It is mounted on a dark metal frame. A white absorbent pad is placed around the master cylinder, and a metal hose is connected to its side. The background shows other parts of the vehicle's chassis.

Absorbent pad found here: Repair needs verified.



Deck Hose fittings leaking: Requires repair.

A close-up photograph of a front axle assembly. The central focus is a large, horizontal, cylindrical metal component, likely a brake drum or hub, which shows signs of wear and discoloration. To the left, a dark, cast metal housing is visible, secured with several bolts. Above the main cylinder, several thick, braided metal hoses are routed across the frame. Below the main cylinder, there are various mechanical components, including what appears to be a suspension bracket with several bolts. The background is slightly out of focus, showing more of the vehicle's chassis and a bright light source, possibly the sun or a workshop light.

Front Axle: Hose need secured in a permanent fashion.




Chaffing area: Lug needs removed or hoses secured.

A close-up photograph of a hydraulic cylinder valve on a yellow machine. The valve is a rectangular metal block with a circular opening on top. A red hydraulic fluid is leaking from the top of the valve. The machine is painted yellow, and there are several silver-colored bolts and nuts visible. A red horizontal bar is at the top of the image.


Right Rear Outrigger Cylinder Valve Leaking.

A close-up photograph of a yellow hydraulic cylinder rod. The rod is the central focus, showing a dark, possibly damaged or worn section. The surrounding area is yellow, likely the body of the cylinder. A metal nut is visible at the top left. The background is slightly blurred, showing some mechanical components and a concrete floor.

Right rear outrigger cylinder rod: Shows signs of damage.



Secure wiring at pinch points.



Possible chaffing issue: Would like to see some type of protection.



Questioned wear area: CraneMaster Rep. explained this is not an issue.


A close-up photograph of a yellow industrial machine. A red rectangular label is affixed to the side of a cylindrical component. The label features the word "STEP" in large, white, bold, sans-serif capital letters with a black outline. To the right of the text is a white downward-pointing arrow with a black outline. The machine's surface shows signs of wear and use. In the foreground, a dark, cylindrical metal part is visible, partially obscuring the lower part of the machine.


STEP ↓

Refer to slide 12.



Hose layout above axles: Hose retainers need to be permanent.





Hand rail needs replaced with another style: Already noted.



Wire ties are not a permanent repair to loose hoses.




Ground connections need to have star washers installed.

A close-up photograph of a concrete surface. In the foreground, there is a metal grate with horizontal ridges. A yellow sticker with the word 'LUB' is partially visible on the grate. The concrete surface is light-colored and shows signs of wear and discoloration. A dark, textured material, possibly a sealant or repair, is visible along the edge of the concrete. A metal component with a bolt is visible in the upper right corner.


Decals are not staying secured: Suggest Stenciling.



Verification needed that suction hose is sufficient.

A close-up photograph showing a blue cable being secured to a yellow surface. The cable is bent at a sharp angle, and a small metal fastener is visible where it is attached. The background is a textured yellow surface, possibly a piece of equipment or a wall. A white text box is overlaid on the bottom center of the image.

Secure wiring at pinch points.



Repair pinched wiring at P clamp.

Exhibit 6

RC35 Warranty/History Report

Delivery Date: Unknown Make: CraneMasters Model: RC35 Serial #: ES10091

Date	Failure
01/15/10	Contract awarded
??/?/13	unit arrives on property
09/25/13	QAAW performs in-process inspection and compiled a list of deficiencies
02/03/15	A Odell assumes CTEM project oversight and compiled/consolidated the lists of existing issues.
02/06/15	unit transported to Branch ave
04/14/15	repair kickoff meeting with crane masters and performed inspection with CM and presented known issues
04/15/15	compiled list of issues found during inspection
4/15/2015 - 4/17/15	CM performed repairs on known issues
05/05/15	QAAW issues report - AR-CTEM-20150423-01F
05/06/15	CM proposes solutions to the boom angle indicator, labeling, counterweight cribber
05/22/15	status meeting with CM, reviewed and approved proposed solutions
05/30/15	CM scheduled to come to work on unit but mechanic was injured off site causing delay
06/16/15	followup meeting with crane masters
06/18/15	QAAW issues report - AR-CTEM-20150618-01F
6/16/05 - 07/30/15	CM installed Turret lock pin, Swing up hand rail above winch, 12V wiring for the camera system, Additional work lights on the boom, Backing plates with reflective tape for outrigger control labels and corrected numerous issues
07/30/15	followup meeting with crane masters
08/25/15	updated Discrepancy list
8/25/15 - 10/21/15	CM continued to repair issues noted on discrepancy list
10/21/15	CM requested the unit be transported to GBLT to touch up the paint. Repairs will continue in GBLT
10/29/15	crane transported to GBLT

11/03/15	Paint readiness and issues reviewed. It was determined that the amount of work needed for paint prep/paint/repairs and testing it would be best if the unit was returned to the vendors facility and completed.
11/20/15	unit transported to Cranemasters in richmond VA
02/12/16	Punch list of repairs delivered and site visit scheduled
02/26/16	Site visit by CTEM, QAAW, CENV
03/16/16	QAAW issues report - AR-CTEM-20160226-01F
03/18/16	Site visit by TRST
04/29/16	Site visit by CTEM, QAAW, CENV
05/10/16	QAAW issues report - AR-CTEM-20160429-01F
06/08/16	on site test plans reviewed and submitted to CM
06/14/16	Site visit by CTEM, QAAW, CENV, TRST canceled due to CM unable to perform Load test
07/26/16	Site visit by CTEM, QAAW, CENV; performed on site test
08/16/16	QAAW issues report - AR-CTEM-20160726-01F
09/13/16	Site visit by CTEM, QAAW, CENV; performed on site test
10/11/16	crane transported to GBLT
12/02/16	towability and emergency stop testing performed in GBLT yard
12/15/16	Weight measurements and derail bar clearance
12/22/16	planned gradeability testing at Fort Totten. Speed and braking testing between Greenbelt and College Park. But canceled due to winch retracting at random. Correspondences sent to CM. CM suspected "wake up line" issues.
01/06/16	moved the unit and before it moved 30 feet it winched the block into the boom and broke the cable and damaged the boom tip. Informed CM immediately
01/18/17	CM came to GBLT to investigate the boom and cable issue. No definitive issue found. Took measurements and will review the data.
01/24/17	CM suspects pilot controls building pressure and proposed solution to add a LMI/pilot cutout manifold
01/26/17	CM and WMATA conference to review the proposal. WMATA concurs and approves with the solution
3/20/17 - 3/21/17	CM repaired the boom tip. Installed the new load line and new manifold.
03/28/17	tested unit on the loop to validate repairs prior to mainline testing
03/30/17	scheduled mainline testing, canceled due to operator working on safetrack

04/05/17	performed main line testing. Speed and gradeability were good but, its brakes would not hold on a hill in the forward direction. Additionally on the way back it lost propulsion and was making a loud grinding noise. We went to rescue the crane but before we got there it started working. back in the yard we were unable to duplicate the issue
04/13/17	CM performed testing to duplicate the issue, reconfigured drive manifold
05/23/17	performed main line testing with a DAQ attached. unit came out of drive 2 times but, otherwise operated as designed. Data was taken back to CM for review
06/05/17	CM completed review of the data and found that the machine left travel mode for seemingly no reason. CM thinks there was an intermittent connectivity issue to one of the interlock sensors. There is Intermittent LMI connectivity . one axle's parking brake release pressure is low in one direction
07/18/17	CM came to replace cables and clean the turret pass through for the LMI circuit in efforts to fix the LMI issues.
09/20/17	CM came to perform CAN diagnostic on the LMI and test leveling system.
12/05/17	CM Installed new counterbalance valve, sequence valve on service brake line and remove parking brake orifices to speed up the application speed.
12/13/17	mecnaincs went to move the unit, While moving the unit the winch engaged pulling the block into the crane boom and snapping the cable. At this point the mechanic was unable to brake and was forced to shut the unit down. Incident 20171226#67763
12/18/17	Tested unit to duplicate the complaint and attempt to isolate the issue.
12/20/17	CM issued report that they were unable to duplicat the issue but found high case drain pressure that required further investigation
1/4/18 - 1/5/18	CM arrived to perform additional testing and found numerous issues.
01/12/18	CM issued report that describes the issues found
2/8/18 - 2/9/18	CM installed and rerouted the pilot drain lines.
02/13/18	CM installed motor case drains and installed filter for motor makeup line. Validated that case pressures were now within the allowable limits.
03/02/18	CM issues status update and action plan to WMATA
Current	Pending WMATA approval of action plan

Exhibit 7



INCIDENT						
Date 12/13/2017	Incident Time 06:30	<input checked="" type="checkbox"/> AM <input type="checkbox"/> PM	Date/Time Reported 12/13/2017 / 06:30	<input checked="" type="checkbox"/> AM <input type="checkbox"/> PM	Worksafe Incident ID# 20171226# 67763	
Location Greenbelt MOW Track 24 shop lead					Incident ID# (From ROCC, BOCC, etc.)	
Type of Incident: <input checked="" type="checkbox"/> Damage to Property		<input type="checkbox"/> Flood	<input type="checkbox"/> Request for Medical Assistance		Injury Class	
Entrapment: <input type="checkbox"/> Elevator <input type="checkbox"/> Disabled Train		Hazardous Material Incident: <input type="checkbox"/> Detector <input type="checkbox"/> Leak <input type="checkbox"/> Spill		<input type="checkbox"/> Injury		<input type="checkbox"/> Fatality <input type="checkbox"/> Medical Treatment
<input type="checkbox"/> Evacuation		Near Miss		<input type="checkbox"/> No Loss		<input type="checkbox"/> First Aid Only <input type="checkbox"/> Restricted Work
<input type="checkbox"/> Fire		Rail Vehicle Collision: <input type="checkbox"/> Collision <input type="checkbox"/> Derailment		<input checked="" type="checkbox"/> Property Damage		<input type="checkbox"/> Loss of Consciousness
				<input type="checkbox"/> Other		<input type="checkbox"/> Lost Time
						<input type="checkbox"/> No Treatment
WMATA PERSONNEL INVOLVED						
Name Raymond Pearl			Age	Employee # or MTPD Badge #		
Phone Number (301) 955-2070	Job Title Mechanic AA CTEM	Department CTEM	Division/Section Greenbelt			
Last Day Worked (prior to) 12/12/2017		Hours Worked (within last 24 hrs) 8		Overtime? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
COMPLETE FOR INCIDENTS WITHIN THE RAIL SYSTEM:						
Train/Vehicle ID RC35	Direction	Track # 24 lead	Car/Vehicle Numbers		Trouble Code	Resp Code
Mezzanine #	AFC Equipment #	Escalator/Elevator #	Entrance	Platform	Track	Room#
COMPLETE FOR INCIDENTS WITHIN THE BUS SYSTEM						
Bus or Tag Number	Vehicle or Tag Number	Block Number	Run Number			
DESCRIBE THE INCIDENT AND PROPERTY/EQUIPMENT DAMAGE						
Provide factual information about the task, actions before and after the incident, the injury causing agent and any damage caused to property or equipment. Provide a diagram(s) and/or photos as attachments. If necessary, provide diagram in this space or on a separate page.						
Moving RC35 to clear the 24 track yard lead, employee started unit and let the unit warm up approximately 5 minutes, started moving the unit in the reverse direction, the unit started to make a crackling sound like abnormal rail wheel noise, the unit was only moving at 1 - 2 mph, attempted to stop the unit and it continued in the reverse direction, moved control to move in the forward direction, it did not reverse direction, at that time a loud bang was heard, the employee immediately shut the unit off with the ignition key. The unit snapped the winch line dropping the headache ball to the track in front of the unit, the cable whipped back to the rear of the unit, that was the result of the loud "bang" heard by the employee. The employee disembarked the unit chocked it and notified his immediate supervisor W. Jones						
EXTERNAL AGENCIES INVOLVED						
<input type="checkbox"/> Fire Dept. - Arrival Time: _____		<input type="checkbox"/> EMS. - Arrival Time: _____				
<input type="checkbox"/> Police - Arrival Time: _____		<input type="checkbox"/> Other _____ - Arrival Time: _____				
Name	Badge Number	Complaint Number	Jurisdiction			
Engine Number	Ambulance Number		Hospital			
ACTIONS TAKEN BY SUPERVISOR.						
Describe immediate changes made to address the incident.						
Interviewed employee and filled out this form. Observed the unit and post episode damage, instructed employee to leave all parts and debris where it landed. Outside temperature was 21 degrees Fahrenheit.						
Form completed by (Signature) William Jones [Signature] WMATA				Date 12/13/2017		
Print name William R. Jones			Employee Number	Phone Number 301-955-2070		
Supervisor (Signature) [Signature]				Date 12/26/17		
Print name Steven Rodman			Employee Number	Phone Number		



Witness or Employee Statement Form

WASHINGTON METROPOLITAN AREA TRANSIT AUTHORITY

USE SEPARATE FORM FOR EACH PERSON

TO BE COMPLETED AND DISTRIBUTED WITHIN 24 HOURS

Page 1 of 1

PERSONNEL INVOLVED (Use This Block For WMATA Employees and Contractors)

Name <i>Ray Pearl</i>		Age [Redacted]	Employee # or MTPD Badge # [Redacted]
Phone Number [Redacted]	Job Title <i>Mechanic AA</i>	Department <i>CTEM</i>	Division/Section <i>Greenbelt</i>
Last Day Worked (prior to) <i>12-12-2017</i>	Hours Worked (within last 24 hrs) <i>8</i>	Overtime? <i>No</i>	

INVOLVED PERSON OR WITNESS (Use This Block For Non-WMATA Involved Person or Witness)

Name <i>Ray Pearl</i>	Phone Number [Redacted]	E-Mail [Redacted] @wmata
Address [Redacted]		

INCIDENT

Date <i>12/13/17</i>	Incident Time <i>06:30</i>	Date/Time Reported <i>12/13/17 06:30</i>	Location <i>Greenbelt New Track 24 stop lead</i>
Incident ID# (From ROCC, BOCC, etc.)		Worksafe Incident #	

What happened prior to the incident?
I was moving RC35 to clear the shop pad on 24 track. did my walk around and checked for any thing hanging off ~~the~~ unit, oil Hyd all ok. started unit let run for 5 min or so my i removed chocks and throw switch on move other unit. so the speed switch can move from bay 23 to bay 24

Describe the incident
I moved other RC35 toward half way over switch, about 10 min went to move RC35 back onto the pad to clear switch heard popping noises coming from out side went to stop move handle to neutral position it kept going applyed brake still kept going creeping backwards toward the bay door, then a loud bang i saw the black fall in front on the ground i instantly turned off ignition, climb out saw cable on ground told supervisor immediately after checking unit

What happened after the incident?
Told supervisor

Form Completed by: (Print Name) <i>Ray Pearl</i>	Date <i>1-3-18</i>
Signature [Redacted]	[Redacted]



Washington Metropolitan Area Transit Authority

Report for incident: **20171226#67763**

Incident Data

Incident Date: 13 December 2017 06:30:00 AM Report Date: 13 December 2017 06:30:00 AM Type: Rail Vehicle Other Class of The Incident: BOCC # : Department: RAIL CMNT Heavy Equip Shop	State: MD Region: PRINCE GEORGE'S Location (Other): Address/Intersection: Street: Cross Street: Cross Street Distance (in feet): Direction to Cross Street:
<p>Description</p> <p>Employee started to move Rail Crane (RC35) and lost propel control and then the winch two-blocked without operator initiation. The winch cable broke, the hook and block fell to the ballast, and the cable whipped over the back of the crane. The employee immediately shut down the crane from the ignition switch and the unit came to a stop without further incident.</p>	
Preferred Phone: 301-955-2102 Alternative Phone: Public Liability: No Patron Involved: No Employee Involved: No Immediate Changes: CTEM disabled the engine start circuit and placed a "Do Not Start" tag on the console with the words "Tow Only" written on the tag. People Impact: None Asset Impact: Torn metal requiring body panel replacement. Total property damage is under \$25,000. Response Level: Level 2 Property Equipment Damage: Explanation For Conclusion: Equipment Complication/Design/Design Specs/Specs needs improvement; Potential People Impact: Potential Asset Impact: Frequency: Risk Index:	Activity Being Performed: (None) Known Facts: While moving the Crane towards the shop the wire rope broke dropping the headache ball between the rails. Equipment: Crane, Key Factors: Work Environment Hot/Cold; Inadequate Technical Design Visibility and Surface Conditions: Lights On, Dawn/Dusk, Clear Hazard Description:

WMATA Vehicles

RC35 (Not Rated)	
Tag : RC35 Asset # : MRC35 Vehicle License Issuing State : VIN Number : 349ECDGE00253 Make : Cranemasters Model : 35 TON Year : 2013 Style : Color : Owner's Name : WMATA Registered Owner's Phone : 202-962-1118 Registered Owner's Address : 600 5th Street NW Washington DC 20001 Insurance Company : Insurance Agent : Insurance Policy # :	Run : MetroAccess Run : Route : On Street : Block : Travel Direction : Total Number Of Occupants : Service Type : Non-Revenue Vehicle State : Towed By : Body Damages : Seat Locations : Speed At Time Of Impact : Skid Marks To Impact : Skid Marks After Impact : Collision Factors :

Employees Involved

Is Injured: No Transported By : Transported To: PPE: Composite Toe Shoes: Worn Properly, Safety Vest: Worn Properly, Seatbelt: Worn Properly Is a witness: No Witness Statement: While performing yard moves crane was moved toward shop apron when he heard a popping noise coming from outside the unit. He went to stop the unit but it kept rolling and the wire rope broke causing the headache ball to fall between the rails. Immediately the unit was turned off and it came to a complete stop. Prior To Incident: Arrived at work on time and was assigned to move equipment in order to get PM work into shop After Incident: Secured unit with chocks and came into the shop to notify his supervisor	Raymond Pearl [REDACTED] Phone: [REDACTED] Address: [REDACTED] City: [REDACTED] Zip Code: [REDACTED] Busines Phone : Busines Address: Driver License Number : License Issued by State : License Expiration Date : Last Day Worked : Hours : Worked Overtime : No Is an Operator: No Vehicle: 20171226#67763 RC35 WMATA MRC35
---	--

I/A Documents

- Original Name : Initial Incident Form 50.688.pdf
Internal Name : [REDACTED]
- Original Name : Employee Statement Form 50.689.pdf
Internal Name : [REDACTED]
- Original Name : Incident Investigation Form - 50 690 Mod.pdf
Internal Name : [REDACTED]
- Original Name : Interview Questions.docx
Internal Name : [REDACTED]


Supervisor (Signature): _____ Date: _____

Print Name: _____ Employee ID: _____ Phone: _____

Employee (Signature): _____ Date: _____

Print Name: _____ Employee ID: _____ Phone: _____










Exhibit 8



May 2, 2018

RE: RC35

Mr. Johnson,

I am writing to inform you that Car Track Equipment Maintenance has resolved to make no further efforts to support the endeavor to meet the requirements of Contract ES10091\GWF for the purchase and acceptance of 35 Ton Rail Crane. Over the previous five years Cranemaster's has attempted to meet the requirements necessary to allow WMATA to safely place the Rail Crane in serviceable use. While Cranemasters has been making efforts to resolve concerns, identified in the Warranty and History Report attached, after five years it remains that multiple significant functional and design items remain unresolved.

It is my recommendation that

[REDACTED]

**Washington
Metropolitan Area
Transit Authority**

Sincerely,

[REDACTED]

Daniel K. Hagan

Exhibit 9



Exhibit 10



SEE OTHER SIDE

REMARKS:

IT IS HERE FOR A PURPOSE
AUTHORITY WILL MEAN
DISCIPLINARY ACTION!

DANGER
DO NOT REMOVE
THIS TAG!









MANAGEMENT'S RESPONSE

M E M O R A N D U M



SUBJECT: Management Assistance Report: WMATA Crane Purchase (MAR-23-0001) DATE: September 9, 2022

FROM: EVP/COO – Brian P. Dwyer Michael Hass Digitally signed by Michael Hass.
Date: 2022.09.15 16:29:20 -0400

TO: OIG – Rene Febles

WMATA's management team has reviewed the Office of Inspector General's (OIG) Management Assistance Report: WMATA Crane Purchase (MAR-23-0001). Since the RC35 crane was purchased, WMATA has improved its Class 2 vehicle design and specification review procedures. These procedures allow WMATA to ensure all Class 2 vehicles, such as this crane, operating on the right of way are doing so as designed and safely. Overall, WMATA agrees with the two (2) recommendations in the report. The actions Car Track Equipment Maintenance (CTEM) have taken to address the recommendations are described below.

1. Follow WMATA safety protocols regarding unsafe equipment and apply them to the RC35.

CTEM has locked out and tagged out the RC35 on September 8, 2022. The keys to the vehicle are secured in a limited access lockbox and the crane is now secured and unusable by WMATA employees.

2. Make a determination if RC35 can be utilized or must be disposed.

WMATA will perform an analysis to identify the most cost-effective way to dispose of the RC35 crane December 15, 2022. Once the analysis is complete, WMATA will work execute the plan to dispose of the RC35 and will notify OIG when disposal occurs.

List of Attachments

1. SOP 202.20 – Class 2 Rail Vehicle Acceptance
2. Equipment Reliability Update 2008-01 – Equipment Failure Service Tags
3. Image 1 – “Do Not Start” and “Out of Service” Tags September 8, 2022

cc: GM/CEO Randy Clarke
Senior Executive Team



OFFICE OF VEHICLE PROGRAM SERVICES

Standard Operating Procedure

CATEGORY Administrative	TOPIC Class 2 Rail Vehicle Acceptance
-----------------------------------	---

SOP NO. 202.20	TITLE Class 2 Rail Vehicle Acceptance Procedure
--------------------------	---

LATEST REVISION NO. 0.0	ORIGINATION DATE 02/02/2022	DATE REVIEW DUE 02/02/2024	EXPIRATION DATE No Expiration
-----------------------------------	---------------------------------------	--------------------------------------	---

LATEST REVISION DATE 02/02/2022	LATEST REVIEW DATE 02/02/2022		
---	---	--	--

SOP APPLIES TO:
CENV

DEPARTMENT/OFFICE/INDIVIDUAL OF PRIMARY RESPONSIBILITY
CMOR, CENV, Deputy Chief Mechanical Officer New Car Programs

EFFECTIVE PAGES/NOTES
Initial document.

DISTRIBUTION All CMOR Offices, MTPD, QICO, SAFE, CVST, TRST	COORDINATION WITH OTHER PUBLICATIONS WMATA SSCPP
---	--

APPROVAL:	DIRECTED BY:
------------------	---------------------

Cameron Akins
Digitally signed by Cameron Akins
 DN: c=US, o=Washington Metropolitan Area Transit Authority, ou=People, cn=Cameron Akins, email=cameron.akins@wmata.com
 WMATA
 _____ Date: _____
 Cameron Akins
 Senior Program Manager
 Vehicle Program Services (CENV)

David F. Sauter
Digitally signed by David F. Sauter c/o Sachit Kakkar
 Date: 2022.02.03 13:40:51 -05'00'
 c/o Sachit Kakkar
 _____ Date: _____
 Sachit Kakkar
 Deputy Chief Mechanical Officer – New Car Program
 Vehicle Program Services (CENV)

Class 2 Rail Vehicle Acceptance Procedure

1. PURPOSE

*This Standard Operating Procedure (SOP) ensures new **Class 2 Rail Vehicles** are specified, designed, and accepted in compliance with Washington Metropolitan Area Transit Authority (WMATA's) Safety and Security Certification Program Plan (SSCPP).*

2. SCOPE

*This procedure describes the steps Vehicle Program Services (CENV) follows, from project initiation to acceptance, to ensure delivery of **Class 2 Rail Vehicles** meeting the highest level of safety, quality, performance, and service.*

3. RESPONSIBILITIES

3.1 Chief Mechanical Officer – Rail/CENV/Deputy Chief Mechanical Officer New Car Programs:

- 3.1.1. Has the responsibility to notify all affected personnel of this SOP or changes to SOP through the WMATA email system.
- 3.1.2. Ensure an email is sent to Metro Transit Police Department (MTPD), Office of Quality Assurance, Internal Compliance & Oversight (QICO), and Department of Safety (SAFE) to notify them of the new or revised SOP that must reside within the **Documentum** domain.
- 3.1.3. The email notification shall identify the link where the SOP resides within the **Documentum** domain.
- 3.1.4. Must submit native (Microsoft Word®) SOP document(s) to Railcar Quality Assurance and Warranty Compliance (RQAW) for final review prior to signatures.
- 3.1.5. Must submit signed Portable Document Format (PDF) SOP to RQAW for final review, prior to being sent to Overhaul Support & Document Configuration Management (ODCM) for upload into **Documentum**.
- 3.1.6. RQAW submits final signed and native documents to CENV, ODCM to upload into **Documentum**.

3.2 Deputy Chief Mechanical Officer(s), CENV:

- 3.2.1 Primary responsibility for administration and compliance with this SOP and its related forms.
- 3.2.2 Ensure all CENV Managers are made aware of this SOP and any changes thereto through Scheduled Meeting and fully comply with all requirements herein.

3.3 Deputy Chief Engineer/Senior Program Manager(s), CENV:

- 3.3.1 Primary responsibility for review and content, to include technical accuracy within the SOP.
- 3.3.2 Primary responsibility for implementation of this SOP within his/her area(s) of responsibility.
- 3.3.3 Ensure CENV personnel are made aware of this SOP and any changes thereto, through the weekly engineering staff meeting and fully comply with all requirements herein.

3.4 Manager(s), CENV:

Class 2 Rail Vehicle Acceptance Procedure

- 3.4.1 All managers shall be responsible for adherence to this SOP and their area(s) of responsibility.
- 3.4.2 Ensure all CENV personnel, under their direct supervision, are made aware of this SOP and fully comply with all policies/procedures herein.
- 3.5 Vehicle Engineers, CENV:**
Responsible for adherence to this SOP and associated forms.
- 3.6 Overhaul Support & Document Configuration Management, (ODCM):**
- 3.6.1 Responsible for retaining and archiving the native (Microsoft Word®) document(s) in **Documentum**.
- 3.6.2 Responsible for the electronic distribution of this SOP through the WMATA email system.

4. DEFINITIONS

- 4.1 Class 2 Rail Vehicle:** A rail vehicle not designed for the transportation of passengers.
- 4.2 Documentum:** Electronic document management system software that provides a single source for documentation storage and controlled access.
- 4.3 Stakeholders:** Departments and personnel that are directly affected by this SOP.
- 4.4 Inspection and Testing Tracking Log:** A tracking log developed, case by case, per project, by SAFE with CENV assistance, based on the technical specifications of the contract.

5. ABBREVIATIONS and ACRONYMS

CENV:	Vehicle Program Services
CMOR:	Chief Mechanical Officer Rail
CTEM:	Car Track Equipment Maintenance
CVST:	Civil & Structural Engineering
MTPD:	Metro Transit Police Department
ODCM:	Overhaul Support & Document Configuration Management
PDF:	Portable Document Format
QICO:	Office of Quality Assurance, Internal Compliance & Oversight
RQAW:	Railcar Quality Assurance & Warranty Compliance
SAFE:	Department of Safety
SOP:	Standard Operating Procedure
SOW:	Scope of Work
SSCPP:	Safety and Security Certification Program Plan
TRST:	Office of Track and Structures
WMATA:	Washington Metropolitan Area Transit Authority

Class 2 Rail Vehicle Acceptance Procedure

6. PROCEDURES

Procedure #	Content
6.1	Project Initiation
6.2	Supplier Design
6.3	Acceptance Testing

6.1 Project Initiation:

- 6.1.1 Distribute project information—draft Scope of Work (SOW) and technical specification—to Office of Track and Structures (TRST), Car Track Equipment Maintenance (CTEM) SAFE, RQAW, Civil & Structural Engineering (CVST) and any other **stakeholders**.
- 6.1.2 Coordinate with respective **stakeholder** departments regarding quality, maintenance, operators' use, and safety to ensure that **stakeholder's** needs are incorporated and that the highest level of performance and service are delivered to WMATA customers.
- 6.1.3 Assist SAFE to evaluate and determine the level of certification required for the project according to the categories defined in the SSCPP.
- 6.1.4 Receive the SAFE Safety Certification Project Assessment form for the project.
- 6.1.5 Ensure that **stakeholder** input, safety, and security requirements, including hazard mitigations and controls, are incorporated into the SOW, design criteria and specifications.

6.2 Supplier Design:

- 6.2.1 Invite stakeholders to participate in design reviews.
- 6.2.2 Ensure the supplier design meets the identified safety and security design and specification requirements.
- 6.2.3 Assist SAFE in the development of an Operational Hazard Analysis and an Inspection and Testing tracking log consistent with WMATA's SSCPP and Safety Risk Management process.
- 6.2.4 Assist SAFE in the identification of safety and security certifiable items and requirements.

6.3 Acceptance Testing:

- 6.3.1 Ensure successful completion of all safety/security related specification and test activities
- 6.3.2 Forward completed and CENV approved test documents to SAFE.
- 6.3.3 Ensure all certifiable items have been verified and send documentation to SAFE.
- 6.3.4 Receive Certificate of Compliance for each package submitted to SAFE.
- 6.3.5 Receive final Safety and Security Certification Verification Report, System Certificate of Compliance at the end of the safety certification for the project.
- 6.3.6 Inform CTEM to update status of fully accepted equipment in Maximo to ready for service.

Class 2 Rail Vehicle Acceptance Procedure

7. SAFETY MANAGEMENT

This document has been created in compliance with WMATA's safety plan and safety policy. Any hazards and risks associated with the processes within this document have been evaluated for safety and have appropriate mitigation strategies established as part of WMATA's overall risk assessment management, where applicable and/or relevant. This document is also subject to monitoring for safety risk mitigation adherence and safety performance, and has effective communication practices in place, including adequate safety training to ensure competencies, and to solicit feedback from the affected employees, where applicable and/or relevant. For further guidance on WMATA's safety plan, visit the Department of Safety and Environmental Management's (SAFE) intranet homepage.

8. REFERENCES

- WMATA SSCPP (**Most recent version**)
- Safety Certification Project Assessment Form

9. RECORDS

N/A

10. ATTACHMENTS

N/A



CTEM Equipment Reliability Update

ERU: 2008-01

Title: Equipment Failure Service Tags

Document #:	ERU2008-01
Models:	All Class 2 Equipment

Revision Number	Reason / Description	Revision Issue Date
0	New	8/14/2020
1	Updated document format	7/19/2021



Washington Metropolitan Area Transit Authority

ERU Number:

ERU Title:

ERU Revision Level: ERU Revision Date:

Approval
Signature:



Digitally signed by Steven Redman
WMATA
Date: 2021.07.19 11:23:42 -04'00'

Steven L. Redman
CTEM Superintendent
Office of Car Maintenance (CMNT) - Car Track Equipment (CTEM)



CTEM

Equipment Reliability Update
ERU: 2008-01

Models:

All Class 2 Equipment

Title:

Equipment Failure Service Tags

This Equipment Reliability Update (ERU) is being issued to all CTEM Personnel.

Condition/Problem: CTEM “Do Not Start” tags have led to equipment in service / out of service issues when applied for ancillary equipment issues to the main console.

Correction: Utilize multiple types of tags for clarification of machine status.

When a machine is unable to be operated a “Do Not Start” tag will be applied to the operator’s console. This indicates the unit is out of service and may not be started.



Do Not Start Tag

R75-10-0040

When a machine has a defective component that does not remove the unit completely from service the following tag configuration will be used.

- An “Out of Service” tag will be applied directly to the component that is unusable listing the issue with the tagged component.



CTEM

Equipment Reliability Update
ERU: 2008-01

Models:

All Class 2 Equipment

Title:

Equipment Failure Service Tags



Out of Service Tag

R76-90-0001

- A “Warning” tag will be applied to the operator’s console listing the defective component and any usage restrictions. This alerts the operator of ancillary equipment concerns that may affect the machines functionality. This tag does not remove a unit from service, only the component listed is out of service.



Warning Tag

R79-60-0001

Mechanics shall fill complete each tag with the following information:

- Issue with machine or component
- Mechanics name, clearly written
- Date tag was installed

DO NOT START THIS MACHINE

SIGNED BY: CTEM
DATE: 9.8.2022
www.accuform.com • reorder# MDT124

DANGER

OUT OF SERVICE

SIGNED BY: CTEM
DATE: 9.8.2022
www.accuform.com • reorder# TAY114

AUTO

1
6

